



Meridian by recovered monumentation
LWN #1 and LWN #4 and recorded
Baker County Survey No. 9-39-27.

LEGEND

- Found monument of record as noted.
- Set 5/8" x 30" rebar.
- [] Record of Baker County Survey No. 9-39-27.
- () Referenced Baker County Deed record.
- LWN Levi W. Nelson Placer Claim, patented.
- Boundary established this survey.

REFERENCES

Baker County Survey No. 9-39-27, filed
March 23, 1979, by W.L. Hanley.
Baker County Deeds:
Book 172 Page 1213
Film Volume 65-07-054
65-22-022
72-28-029
83-33-060

SURVEY NARRATIVE

THIS SURVEY WAS PERFORMED AT THE REQUEST OF DICK HENTZE, LANDOWNER, FOR THE PURPOSE OF MARKING THE BOUNDARY SHOWN ON THIS PLAT TO FACILITATE FENCE CONSTRUCTION.

THE BASIS OF THIS SURVEY IS THE RECOVERED MONUMENTATION FOR CORNER NOS. 1 AND 4 OF THE LEVI W. NELSON PLACER CLAIM AND BAKER COUNTY SURVEY NO. 9-39-27, FILED MARCH 23, 1979, BY WHICH THE MERIDIAN WAS DETERMINED. ALL DEED REFERENCES INCORPORATED IN THE EVALUATION OF THIS PROJECT AT SOME POINT REFER TO THE SAID LEVI W. NELSON PLACER CLAIM AND BEARINGS IN THOSE RECORDS ARE ROTATED TO ESTABLISH A COMMON MERIDIAN FROM WHICH THE MONUMENTATION OF THIS SURVEY WAS ESTABLISHED.

MAP OF SURVEY

IN THE NE¹/₄NW¹/₄ SECTION 8, T.9S., R.39E., W.M.
Surveyed Aug. 6th, 1984

FOR DICK HENTZE

Scale 1"=100'

FILED Nov. 14, 84

BAKER COUNTY SURVEYOR

SURVEY NO. 9-39-58

REGISTERED
PROFESSIONAL
LAND SURVEYOR
William L. Hanley
BAKER, OREGON
OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639