

T. 9 S., R. 39 E., W.M., SECTION 6

C-¼, SECTION 6
FD. 1-3/8" SMOOTH PIN

T. 9 S., R. 38 E., W.M.
T. 9 S., R. 39 E., W.M.



N½ GOVT. LOT 2 OF THE SW¼

N½ GOVT. LOT 1 OF THE SW¼

NW¼ SE¼

APPROX. P.I. ROAD
FD ½" REBAR

PER DESCRIPTION BY
COUNTY SURVEYOR.
APPROVED BY ROAD
VIEWERS JUNE 4, 1902.

1902 SURVEY
AS-BUILT
BAKER COUNTY SURVEY NO. 9-39-268
WITH ROTATIONAL ERROR CORRECTED.

REFERENCES

BAKER COUNTY SURVEY NO. 9-39-19.
BAKER COUNTY SURVEY NO. 9-39-208 M.P.
BAKER COUNTY SURVEY NO. 9-39-268.

☉ CURVE DATA

Δ = 8° 21' 37"
R = 750.00'
S = 54.82'
L = 109.44'
Lc = S. 51° 16' 15" W.,
109.34'

S½ GOVT. LOT 2 OF THE SW¼

P.O.B.
BAISLEY
DITCH

S½ GOVT. LOT 1 OF THE SW¼

☉ CURVE DATA

Δ = 11° 00' 35"
R = 1000.00'
S = 96.37'
L = 192.15'
Lc = S. 49° 56' 46" W.,
191.86'

SOUTHWEST CORNER SEC. 6
FD. 3" BLM BRASS CAP MON.
0.61' SOUTH &
1.33' EAST OF TRUE
CORNER LOCATION AS
PER BCS #9-39-19.

CATTLE
GUARD

NARRATIVE

This survey of a portion of Marble Creek Road is made at the request of the Baker County Road Department. The purpose of this survey is to map the existing driven road from its intersection with the Baisley Ditch to the South line of Section 6, T. 9 S., R. 39 E., W.M.. The surveyed portion of this road is shown hereon with solid lines 60 feet in width. Shown on this drawing is the superimposed roadway described by County Surveyor D.W.C. Nelson, approved June 4, 1902, by County Road Viewers. Also shown on this drawing is the existing road from East of the C-¼ corner of said Section 6, to the crossing of the Baisley Ditch. This section of Marble Creek Road was mapped by Baker County Survey No. 9-39-268, which was found to contain a rotational error. The rotation error has been corrected and shown correctly hereon.

MAP OF SURVEY

A PORTION OF MARBLE CREEK ROAD
SECTION 6, T. 9 S., R. 39 E., W.M.
BAKER COUNTY, OREGON

Surveyed April 10 & May 3, 2000
for Baker County Road Dept.

Scale: 1" = 200'

HANLEY ENGINEERING, INC.
2043 MAIN STREET
BAKER CITY, OREGON

REGISTERED
PROFESSIONAL
LAND SURVEYOR

THOMAS J. HANLEY
OREGON
JULY 13, 1979
THOMAS J. HANLEY
1817

Renews June 30, 2001

FILED MAY 8, 2000
BAKER COUNTY SURVEYOR
SURVEY NO. 9-39-274