


CORNER RESTORATION

CORNER: C-W1/16 SEC. 10, TWP. 9 S., RANGE 39 E., W.M.

ORIGINAL SURVEY BY: NOT

SURVEY NUMBER: PREVIOUSLY

DATE: ESTABLISHED



ORIGINAL DESCRIPTION: NONE

RESTORATION BY, STAMP AND DATE:

Jason L. Hatfield, PLS

Benchmark Land Surveying, Inc.
2101 Main Street, Suite 223
Baker City, OR 97814

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
NOVEMBER 30, 2007
JASON L. HATFIELD
#69454

EXPIRES: 6/30/2015

Work performed April 16, 2014

See Record Map of Survey No. 9-39-294

DESCRIPTION OF MONUMENTS AND ACCESSORIES SET AND METHODS USED:

At the corner point as located by survey, I set a 5/8"x15" iron pin 16" in the ground, with attached 1 1/2" diameter aluminum cap marked as shown. This corner falls in the gravel surface of Rouen Road.



From which, I SET THE FOLLOWING REFERENCE POINTS:

- ▶ A 5/8"x30" iron pin bears N.00°02'19"E., 15.00 ft., with attached yellow plastic cap marked "BENCHMARK SURVEYING"
- ▶ A 5/8"x30" iron pin bears N.50°30'W., 24.41 ft., with attached yellow plastic cap marked "BENCHMARK SURVEYING"

Used RTK GPS to measure bearing and distance to the RP's.

FILED April 21, 2014
BAKER COUNTY SURVEYOR
SURVEY NO. 9-39-295