

Point on R/W bears N 44° 48' W., 1802.2'
from SE cor. Sec. 29. Set Iron Pipe

Beginning at a point on the South line of Section 29,
T. 9 S., R. 40 E., W. M., N. 89° 44' W., 1702.4 ft. from the South-
east corner of Sec. 29 and also being on the Easterly right-
of-way line (50 feet distant from center line) of State High-
way No. 7; thence Northerly along the Easterly right-of-way
line of said highway to a point which bears N. 44° 48' W., 1802.2
feet from the said Southeast corner of Sec. 29, said point being
50 feet right of Engineer's Highway Station 471+24.07; thence
S. 33° 15' E., 101.4 feet; thence along the Westerly bank of Powder
River to intersection with the South line of Sec. 29; thence West,
20 feet, more or less, to the point of beginning, containing 2.6
acres.

SW 1/4 SE 1/4

T. 9 S., R. 40 E., W. M.

1/4 Cor. Hwy. Coordinates:
52,509.34 N.
16,926.71 E.

SEC. 29
SEC. 32

Set I.P. 50' 50' 336.9' S. 89° 44' E., 1365.5'
to SE Cor. Sec. 29

Hwy. Coordinates:
52,496.85 N.
19,657.68 E.

TRACT SURVEY

Surveyed February 17, 1955
SCALE 1" = 200'

Survey for F. De Roest

FILED 3-10-55

BAKER COUNTY SURVEYOR

SURVEY NO. 9-40-5

