



Located by hwy. stationing { Sec OSHD Drg No. GB-6-15 Baker-Homestead Hwy. }
 Set 1/2" rebar N. 88° 05' 14" E., 2,656.82'

Set 1/2" rebar on line bet. sec. cors. at point intersected by N-S mid-sec. line fence. N. 88° 05' 14" E., 2,647.30'

Found, a 2-inch iron pipe between ditch and road, S. 02° 24' E., 2,633.5 ft. from reestablished SW corner of Sec. 1

Found, the S 1/4 cor. stone for Sec. 1 & reestablished the sec. corner by intersecting county road (built on East line of Sec. 2) with line connecting SW cor. Sec. 2 & S 1/4 cor. Sec. 1

MAP OF SURVEY

THE N 1/2 SW 1/4 SE 1/4 SE 1/4 SECTION 2, S 1/4 cor. Sec. 1
 T. 9 S., R. 40 E., W. M.

Feb. 1, 2, 7-9, 1973
 DUANE MORRIS

Scale 1" = 1/8 mile = 660'

City of Baker Grid of 1970. Rotate 1° 38' to conform to OSHD grid.

FILED Feb. 22, 1973
 BAKER COUNTY SURVEYOR
 SURVEY NO. 9-40-13-

