



The original plat of FISHERS ADDITION does not designate alley width in BLOCK A, nor the width of AUBURN AVENUE. The South line of VALLEY AVENUE is the control for this BLOCK A. Divergence of  $0^{\circ} 41' 07''$  between VALLEY AVE. and AUBURN AVENUE lines of monuments yields a variable width of AUBURN AVE, being 34.20 ft. North of line of monuments at Southwest corner of Lot 1 and 38.38 ft. North of line of monuments at the Southwest corner of Lot 8. The South part of AUBURN AVE. (lying South of the line of monuments and the section line between Secs. 16 and 21) is not shown, this survey. An early city engineer's map (about 1920 vintage) of this addition indicates the alley width of 15 feet in BLOCK A, and a recent Tax Commission map shows this alley width to be 14 feet. I have determined the 15 ft. width is correct.

### SURVEY IN BLOCK A FISHERS ADDITION TO BAKER, ORE.

MAR. 30, APR 1 & 3, 1970  
SCALE 1" = 50'  
Survey for Erhardt Buchfinck

FILED April 16, 1970  
BAKER COUNTY SURVEYOR  
SURVEY NO. 9-40-23 BC

