

5. I found a stone 18" x 8" x 8" marked  $\frac{1}{4}$  on the north face, as described in the G.L.O. notes for the  $\frac{1}{4}$  corner common to Sections 29 & 32, T 9 S R 40 E, lying with marks face down. I set the original stone upright in place and placed a mound of stone about its base.
6. I found original stone 18" x 10" x 8" as described in the G.L.O. notes with a 1" iron pin alongside in a mound of stone for the Section corner common to Sections 29, 30, 31 & 32, T 9 S R 40 E.
7. I found original stone 17" x 8" x 8" as described in the G.L.O. notes in a mound of stone for  $\frac{1}{4}$  corner common to Sections 33 & 34, T 9 S R 40 E.
8. I found the original stone 17" x 10" x 10" marked with 2 notches on west face and 4 notches on east face as was set by Thompson and Chaplin on May 27, 1864 under Contract No. 104, for the Section corner common to Sections 32 & 33 T 9 S R 40 E and Sections 4 & 5, T 10 S R 40 E.
9. Then I followed T. W. Davenport's survey of July 20, 1863 east along the township line between Township 9 & 10 south Range 40 E. I found no evidence of original corners along this line until I reached the Section corner common to Sections 35 & 36, T 9 S R 40 E and Sections 1 & 2, T 10 S R 40 E, WM, of which I found a mound of stone but no evidence of any wooden post as is described in the GLO notes. I also found a mound of stone as described in the GLO notes for the  $\frac{1}{4}$  corner common to sections 36 & 1, T 9 & 10 S R 40 E.

With these 3 corners along the township line I was then able to restore the Section corner common to Sections 35 & 34, T 9 S R 40 E and Sections 2 & 3, T 10 S R 40 E, by using the GLO calls to a break which was noted to be 0.75 chains east of, and 0.75 chains north of the section corner. Using these calls and making a judgement as to where the original creek channel was in the year 1863, I then established a point ~~of~~ which I felt was as nearly as possible to being where the original section corner had been set. I then set a 2" x 30" galv. iron pipe with a stamped brass cap to be the Section corner common to Sections 34, 35 & 2, 3, T 9 & 10 S R 40 E. I then set the missing  $\frac{1}{4}$  corners and Section corner by proportionate measurements along the township line.

I then made an extensive search for the  $\frac{1}{4}$  corner common to Sections 34 & 35, T 9 S R 40 E, of which I found no evidence of the original corner stone. I found an existing fence line intersecting at a rock jack with an old fence line to the west. This point was much to far east, by approximately 80 feet, of being near the original  $\frac{1}{4}$  corner, thus in my judgement was not acceptable evidence. I found some monuments of record along the east-west line through the center of Section 34, and using these monuments and the section corner monuments I restored this  $\frac{1}{4}$  corner as nearly as possible to its original position.

March 20, 1986

9-40-37