



**LEGEND**

- FOUND MONUMENT AS NOTED
- SET  $\frac{3}{8}$ " x 30" REBAR
- ( ) ORIGINAL PLAT RECORD

**NARRATIVE**

Found, the South quarter Sec. 20 monument and a nail marking the center of Section 20 at the proper bearing and distance (N. 89° 26' E., 242.7 feet) from the intersection of 9th Street with Indiana Avenue, as referenced on the HILLCREST ADDITION plat of 1938 by H. L. Melton.

The distance between the found nail and quarter corner monument is 2647.78 feet. The JACKSON ADDITION plat shows 2648.0 feet. The difference of 0.22 feet was proportioned between Tract "A" and Tract "J" of JACKSON ADDITION. The East-West distances from mid-section line ( East line of 9th Street ) to Foothill Drive are those of record on the JACKSON ADDITION map.

FILED March 25, 1981  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 9-40-174 174

**MAP OF SURVEY**  
 IN TRACT 'G' JACKSON'S ADD'N  
 Surveyed Feb. 25, 1981 1"=100'  
 For Melvin Spence

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
*James D. Hanley*  
 OREGON  
 SEPTEMBER 23, 1977  
 JAMES D. HANLEY  
 1206