

# NARRATIVE

This survey for Dale Hoopes was for the purpose of marking on the ground the corners of Lot 6, Block 2, Levens Addition to Baker, Oregon. Monuments and monument references along 10th Street were destroyed during street widening and new curb construction in about the late 1950's. City Engineer Paul Revis allowed O.S.H.D. to remove curbs containing lead plugs for cross reference without ties for restoration. I have used the sidewalk location along 10th St. for the approximate relocation of property lines (1 foot from inside edge of walks), which closely agrees with platted block distances for Block 7, Levens Addition. Platted block distances are used herein for reconstruction of 10th St. & as nearly as now possible. The found monument near the SE corner, Lot 1, Block 2 is 39.52 ft. N. and 40.98 ft. W. of city monument @ 9th and 'A' Streets.

## LEGEND

- Set 5/8" x 30" rebar w/ plastic cap mkd, 'HANLEY ENGRG, PLS 1206'
- Found 3/4" pipe
- Found city monument in box

MAP OF SURVEY  
 LOT 6, BLOCK 2  
 LEVENS ADDITION  
 TO BAKER, OREGON  
 FOR  
 DALE HOOPES

SURVEYED JUNE 6<sup>th</sup>, 1988  
 SCALE: 1" = 100'

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*James D. Hanley*  
 OREGON  
 SEPTEMBER 23, 1977  
 JAMES D. HANLEY  
 1206

HANLEY ENGINEERING  
 BAKER, OREGON

FILED 8-17-88  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 9-40-271

