



NARRATIVE

The purpose of this survey for D.R. Johnson Lumber Company was to mark on the ground the southwest corner of Block 28, Levens Addition, and the North line of "C" Street between Chico (17th) and the U.P.R.R. Monumentation along 17th Street between Campbell and "H" Streets and at the intersection of 13th and "C" Streets was recovered as control points for this survey. The width of Chico Street varies from 80' wide at Campbell Street to 113.0' wide at "H" Streets. Due to lack of monumentation along "C" Street between Chico (17th) and 13th Street plat distance controls block location, resulting in Chico Street centerline varying somewhat from tangent between Campbell and "H" Streets.

LEGEND

- Found city monument in steel box as noted
- Set 5/8"x30" rebar with yellow plastic cap marked "HANLEY ENGRG PLS 1206"
- /// Marked line with steel fence posts

MAP OF SURVEY
IN
LEVENS ADDITION, BAKER, OR.

Surveyed August 5 and 12, 1988
Scale 1" = 200'

BASIS OF BEARING
CHICO STREET (17TH)
BETWEEN "H" AND
CAMPBELL STREETS
BEARS N. 0° 00' 26" W.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley

OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

HANLEY ENGINEERING
2043 MAIN STREET
BAKER, OREGON

FILED MAY 23, 1990
BAKER COUNTY SURVEYOR
SURVEY NO. 9-40-308