



**NARRATIVE**

THE PURPOSE OF THIS SURVEY WAS TO MARK ON THE GROUND THE CORNERS OF THE PARCEL DESCRIBED AS BLOCK 34, B.W. LEVEN'S ADDITION TO BAKER CITY, COUNTY OF BAKER AND STATE OF OREGON, TOGETHER WITH THE NORTH ONE HALF OF "F" STREET ADJOINING SAID BLOCK ON THE SOUTH, VACATED BY ORDINANCE NO. 2745, RECORDED JULY 14, 1977, IN DEEDS 77 28 123.

AND THE WEST 100 FEET OF THE NORTH 100 FEET OF BLOCK 35, SAID ADDITION TO BAKER CITY, TOGETHER WITH THAT PORTION OF THE SOUTH HALF OF "F" STREET EXTENDING ALONG THE ENTIRE LENGTH OF THE NORTH LINE OF SAID BLOCK 35, VACATED BY ORDINANCE NO. 2745, RECORDED JULY 14, 1977, IN DEEDS 77 28 123.

CONTROLLING MONUMENTATION ALONG 9th STREET AND 11th STREET WERE RECOVERED. NO MONUMENTATION WAS RECOVERED ALONG 10th STREET. THE INTERSECTIONS OF 10th AND "E", 10th AND "F", AND 10th AND "G" STREETS WERE RELOCATED AT THEIR PROPORTIONED POSITIONS USING ORIGINAL PLAT DISTANCES AND ACTUAL MEASURED DISTANCES; THESE LOCATIONS WERE NOT MONUMENTED.

**LEGEND**

- Set 5/8" x 30" rebar w/ plastic cap marked, HANLEY ENGR. PLS 1206'
- ◻ Found city monument in box
- Found city monument w/out box
- Parcel boundary
- ( ) Plat distance

**MAP OF SURVEY  
IN BLOCKS 34 & 35, LEVEN'S ADD'N  
TO BAKER CITY, OREGON**

SURVEYED: JULY 11, 1990 SCALE: 1" = 50'  
FOR JOE RUDI



**HANLEY ENGINEERING  
BAKER CITY OREGON**