


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T.9S.,R.40E. (Z-9)
T.10S.,R.40E. (A-9)

History of original corner establishment:

Corner was originally set by Timothy W. Davenport under G.L.O. Contract No. 102, dated July 20, 1863. G.L.O. record states: "set post corner to secs. 4, 5, 32 and 33, made mound of rock." In 1900, Ira Hoffman, then current Baker County Surveyor, visited this corner as documented in Baker Co. Surveyor Book No. 2, page 17. In this entry he does not describe the corner. In Baker Co. Surveyor Book No. 35, page 40, dated 1920, the corner is described as "found stone 4" x 6" x 12" loose on ground alongside old mound, set said stone in mound." I believe Ira Hoffman perpetuated this corner in 1900 by marking the stone which was later found in 1920 and 1993.



Description of corner evidence found:

Found 7" x 8" x 14" stone set 4" into the ground, marked with 4 chisel marks on East face and 2 chisel marks on West face. A 1/2" dia. pipe has been driven 0.2' West from the corner stone.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as previously marked by the found stones location, set 1 1/4" x 30" galvanized iron pipe 20" into the ground, with 2 1/2" dia. brass cap marked as shown in the corner diagram. From this point bear the following objects:

A 5/8" x 30" rebar set flush with the ground bears N. 47° W., 20.00 feet with yellow plastic cap marked "HANLEY ENGR. PLS 1206" attached.

A 5/8" x 30" rebar set flush with the ground bears N. 43° E., 20.00 feet with yellow plastic cap marked "HANLEY ENGR. PLS 1206" attached.

A 5/8" x 30" rebar set flush with the ground bears S. 47° E., 20.00 feet with yellow plastic cap marked "HANLEY ENGR. PLS 1206" attached.

A 24" x 24" stone firmly in the ground, projecting 12" above the ground bears S. 77° W., 29.30 feet, marked "X" in top.

Buried stone and 1/2" pipe 1.0 feet North of the monument.

I hereby certify that the above described corner was established under my direct supervision as witnessed by Larry McBroom and Kyle Byrne.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

Renewal date Jan. 1, 1994

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by

(COUNTY OFFICIAL)

(DEPUTY)

FILED Dec 22, 1993
BAKER COUNTY SURVEYOR
SURVEY NO. 9-40-388