



STREET

TEMP. REFERENCES  
WOOD HUB & TACK

RESET 5/8" X 30" REBAR  
IN CITY MONUMENT BOX.  
PLASTIC CAP MARKED  
"CITY OF BAKER PLS 2446"

HORIZ ANGLE 145°05' 13"  
HORIZ ANGLE 206°42' 32"

(80')

"H"

79.85'

(80')

STREET

(60')

BIRCH

5/8" REBAR W/YELLOW  
CAP MARKED "HANLEY  
ENGR. PLS 1206"

FILED II-1-96

BAKER COUNTY SURVEYOR

SURVEY NO. 9-40-442

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Thomas D. Fisk*

OREGON  
JULY 25, 1990  
THOMAS D. FISK  
# 2446

RENEWAL DATE 1/1/98

### NARRATIVE

THE PURPOSE OF THIS MAP IS TO DOCUMENT THE REPLACEMENT OF AN OBLITERATED 1/16 CORNER MONUMENT. DURING THE EXCAVATION PHASE OF THE 1996 BIRCH STREET CONSTRUCTION PROJECT IT BECAME NECESSARY TO REMOVE THE RECORD 1/2" REBAR. ITS LOCATION WAS REFERENCED AS SHOWN. AFTER BIRCH STREET CONSTRUCTION WAS COMPLETED A 5/8" REBAR WAS SET IN THE SAME LOCATION AS PREVIOUSLY OCCUPIED BY THE ORIGINAL MONUMENT. THE ORIGINAL 1/2" REBAR WAS SET BY HANLEY ENGINEERING AND MARKED WITH A YELLOW PLASTIC CAP INSCRIBED "RPE 2808". THE NEW 5/8" REBAR IS MARKED WITH A YELLOW PLASTIC CAP INSCRIBED "CITY OF BAKER PLS 2446". THIS MONUMENT IS SET IN A STANDARD STREET MONUMENT BOX.

BAKER CITY, OREGON

Office of Technical Services

REMONUMENTATION OF  
THE S.E. COR. SW1/4SE1/4 SEC. 9  
T. 9 S., R. 40 E., W.M.

DATE: OCTOBER 1996

SCALE 1" = 30'

DRAWN: T. FISK

FILE: C:\CAD\MAPS\MON

9-40-445