

- FOUND 5/8" IRON PIN WITH NO CAP BELOW GROUND IN A CAST IRON CITY MONUMENT CASE
- FOUND PK NAIL OF UNKNOWN ORIGIN SET IN ASPHALT STREET SURFACE AS ACCEPTED IN SURVEY NO.'S 9-40-610 AND 9-40-698
- FOUND 5/8" IRON PIN WITH ATTACHED YELLOW PLASTIC CAP MARKED "HANLEY ENGR. PLS 1206" FROM SURVEY NO. 9-40-207
- FOUND 5/8" IRON PIN WITH NO CAP FROM SURVEY NO. 9-40-207
- FOUND 5/8" IRON PIN WITH YELLOW PLASTIC CAP FROM SURVEY NO. 9-40-698
- O SET 5/8"X30" IRON PIN WITH ATTACHED YELLOW PLASTIC CAP MARKED BENCHMARK SURVEYING
- FOUND 5/8"X30" IRON PIN DISTURBED BY CONSTRUCTION ACTIVITIES. RE—SET AND ATTACHED PLASTIC CAP MARKED BENCHMARK SURVEYING
- () RECORD DISTANCE FROM PLAT OF PACIFIC ADDITION
- [] RECORD BEARING AND DISTANCE FROM SURVEY NO. 9-40-207
- 1[] RECORD BEARING AND DISTANCE FROM SURVEY NO. 9-40-610
- 2[] RECORD BEARING AND DISTANCE FROM SURVEY NO. 9-40-698

THIS SURVEY WAS PERFORMED AT THE REQUEST OF KENNETH AND SUSAN YEN. THE PURPOSE OF THIS SURVEY WAS TO REESTABLISH THE NORTHWEST CORNER AND MONUMENT THE SOUTHWEST AND SOUTHEAST CORNERS OF THE YENS' PROPERTY AS DESCRIBED IN DEED NO. B11 49 0195.

A SEARCH WAS MADE OF THE AVAILABLE RECORDS PERTAINING TO THIS SURVEY. FIELD MEASUREMENTS WERE MADE TO LOCATE APPURTENANT MONUMENTS SHOWN ON RECORD SURVEY NO.'S 9-40-207, 9-40-610 AND 9-40-698.

WE FOUND THE MONUMENT WHICH HAD BEEN SET DURING SURVEY NO. 9-40-698 AT THE NORTHWEST CORNER, WHICH HAD BEEN DISTURBED DURING CONSTRUCTION ACTIVITIES. I RESET THIS PIN IN ITS RECORD LOCATION. I ACCEPT ALL THE OTHER FOUND MONUMENTS OF RECORD AND SET NEW MONUMENTS ACCORDING TO THE EVIDENCE FOUND. AT THE REQUEST OF MR. YEN, WE ALSO SET A PIN ALONG THE WEST PROPERTY LINE, AS SHOWN.

REFERENCES

PLAT OF PACIFIC ADDITION TO BAKER CITY

BAKER CITY ORDINANCE NO.'S 2892 & 2910

RECORD MAP OF SURVEY NO.'S 9-40-207, 9-40-610, 9-40-693 AND 9-40-698

DEED RECORD INSTRUMENT NO.'S B11 49 0195, B04 41 0118, B11 48 0051, 84 41 070, 88 32 052 AND B12 03 0150

