

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 14" x 8" x 6" buried 10 inches in the ground, marked 1/4 on the West side, for the one quarter corner common to Sections 9 & 10, T 9 S, R 41 E W.M. Dug pits 18" x 18" x 12", 5 1/2 feet distance North and South of the stone and placed a raised mound of earth 1 1/2 feet high, 3 1/2 feet at base alongside.

Apparently a mound stone was placed at the 1/4 corner location by unknown sources at some later date, because in 1952 the County Surveyor James D. Hanley visited this 1/4 corner, making note he found a mound of stone. He had confirmed the mound of stone was the true corner and used it in a survey he made at that time and recorded as Survey Number 9- 41 - 1, dated October 15, 1952. He apparently missed seeing the markings on the 1/4 corner stone.

## Description of Corner Evidence Found:

At this corner location I found a marked Basalt stone, measuring 14" x 10" x 5" as well as a mound of stone. The Basalt stone closely fits the dimension of the stone W. B. Barr said he set. The marking 1/4 is dimly visible on the face of the stone as shown in the accompanying photo. W. B. Barr does not mention placing a mound of stone around this corner stone.

## Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this 1/4 corner, at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument with the markings facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on December 7, 2012.



At this Quarter Corner location I found a marked Basalt stone that measures 14"x 10"x 5" and a mound of stone. The marked stone closely agreeing as described in W. B. Barr's field notes. Notice the markings 1/4 as I have highlighted using a black lumber marker to out line the dimly visible chisel marks.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. Notice the reference pin located in the background near the top center of photo.



Brass Cap as stamped.

This 1/4 corners handheld GPS geographic position.  
44° 47' 45.660" N, 117° 41' 9.480" W NAD83.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James H. Hambleton*

OREGON  
JULY 10, 1964  
JAMES H. HAMBLETON  
645

Renews June 30, 2012