CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of Original Corner Establishment:

This section corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a post 4 feet long, 4 inches diameter with marked stone, 2 feet in ground for corner to sections 9, 10, 15 & 16. Marked T 9 S, S 10 on NE face, R 41 E, S 15 on the SE face, S 16 on the SW face and S 9 on the NW face, with 4 notches on the S. and 3 notches on the E. edges. (I am assuming he was referring to the stone when he mentions the notches.) Dug pits 18" x 18" x 12", 5 1/2 feet distance in each section and placed a raised mound of earth 2 feet high, 4 1/2 feet at base alongside.

In 1952 County Surveyor James D. Hanley had determined this corner to be lost, thus he proceeded to restore the corner by survey. His recorded Survey Number 9 - 41 - 1, dated October 15, 1952 shows he set a 1" x 30" iron pipe for the section corner common to Sections 9, 10, 15 & 16, T 9 S, R 41 E W.M.

Description of Corner Evidence Found:

There are ambiguous statements in W. B. Barr's field notes pertaining to this section corner, rendering it quite confusing as to what Mr. Barr actualy did set for this corner. However this actually makes little difference because by 1952 several construction activities in the immediate area had destroyed the section corner. A record survey, Survey Number 9 - 41 - 1, dated October 15, 1952 by County Surveyor James D. Hanley, shows it was necessary to restore this corner as a lost corner. He set a 1" x 30" iron pipe at this location. I found the 1" x 30" iron pipe in place, which was in good condition, with a small mound of stone around the pipe. It is located on the edge of a drainage ditch for runoff from the county road at a cattle guard.



To perpetuate this section corner at the exact location of the iron pipe, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The iron pipe set by County Surveyor was buried on the North side against the new monument. I placed a large mound of stone around the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North 20.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South 20.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 2 inches above the ground surface. Iron pin is located near a high traffic area.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East 20.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West 20.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 2 inches above the ground surface. Iron pin is located near a high traffic area.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on December 8, 2012.



Found 1" x 30" iron pipe set by County Surveyor James D. Hanley in 1952. It was accompanyied by a small mound of stone as shown.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. Notice the reference pin located to the North in the background near the top center of photo.



Brass Cap as stamped.

This Section corners handheld GPS geographic position. $44^{\circ}~47^{\circ}~19.500^{\circ}~N,~117^{\circ}~41^{\circ}~9.120^{\circ}~W~NAD83.$

PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2012

AKER COUNTY SURVEYOR
SURVEY NO. 9-41-11