CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 12" x 8" x 6" buried 8 inches in the ground, marked 1/4 on the West side, for the one quarter corner common to Sections 15 & 16, T 9 S, R 41 E W.M. Dug pits 18" x 18" x 12", 5 1/2 feet distance North and South of the stone and placed a raised mound of earth 1 1/2 feet high, 3 1/2 feet at base alongside.

In 1952 the County Surveyor James D. Hanley visited this 1/4 corner, making note he found a marked stone. He had confirmed this stone as the true 1/4 corner and used it in a survey he made at that time and recorded as Survey Number 9- 41 - 1, dated October 15, 1952.

Description of Corner Evidence Found:

At this corner location I found a Basalt stone, measuring 11" x 10"x 9" as well as a steel fence post standing alongside. The stone closely fits the dimension of the stone W. B. Barr said he set. The marking 1/4 is clearly visible on the face of the stone as shown in the accompanying photo. No other stone are available in the immediate area.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 7 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument with the markings facing the monument. There are no stone available in the area; therefore the monument stands alone. I then reset the steel fence post alongside the monument to aid in locating the monument in the future. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on December 8, 2012



At this Quarter Corner location I found a marked Basalt stone that measures 11"x 10"x 9", the marked stone closely agreeing as described in W. B. Barr's field notes. Notice the markings 1/4 as I have highlighted using snow to out line the clearly visible chisel marks.



Buried monument to within 7 inches of the surface.

Original stone was placed below the surface on the West side of the Brass Cap. No other stone was available in the area. I then reset the steel fence post alongside the monument to aid in locating the monument in the future. Notice the reference pin located in the background near the top center of photo.



Brass Cap as stamped.

This 1/4 corners handheld GPS geographic position. 44° 46' 53.340" N, 117° 41' 10.260" W NAD83.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1964

JAMES H. HAMBLETON
645

Renews June 30, 2012

BAKER COUNTY SURVEYOR