
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Volcanic rock 18" x 16" x 9" buried 12 inches in the ground, marked 1/4 on the North side for the one quarter corner common to Sections 16 & 21, T 9 S, R 41 E W.M. Dug pits 18" x 18" x 12", 5 1/2 feet distance East and West of the stone and placed a raised mound of earth 1 1/2 feet high, 3 1/2 feet at base alongside.

Description of Corner Evidence Found:

At this corner location I found a Volcanic stone, measuring 18" x 16"x 9" as well as a small mound of stone, the stone fits the dimension of the stone W. B. Barr said he set. I could identify only a portion of the chisel marking 1/4 as it is very dim but visible on the very rough surface of the North face of the stone. Stone and mound is as shown in the accompanying photo. W. B. Barr does not mention placing a mound of stone around this corner stone. The small mound of stone is from unknown origin.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument. The markings are facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on December 8, 2012.



Found a very rough Volcanic stone 18" x 16" x 9" fitting W. B. Barr's description of the stone he set. Dimly visible markings can be identified on the North face of the stone. An additional small mound of stone is present at this corner location.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. Notice the reference pin located in the background near the top center of photo.



Brass Cap as stamped.

This 1/4 corners handheld GPS geographic position. 44° 46' 26.940" N, 117° 41' 47.460" W NAD83.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1964

JAMES H. HAMBLETON
645

Renews June 30, 2012

BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-13