

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of Original Corner Establishment:

This section corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 16" x 14" x 12" buried 11 inches in the ground, for corner common to Sections 15,16, 21 & 22, T 9 S, R 41 E W.M. Marked with 3 notches on the South and 3 notches on the East edges. Dug pits 18" x 18" x 12", 5 1/2 feet distance in each section and placed a raised mound of earth 2 feet high, 4 1/2 feet at base alongside.

## Description of Corner Evidence Found:

At this corner location I found a Basalt stone lying on the surface measuring 16" x 13" x 12", which closely fits the dimension of the stone W. B. Barr said he set. The stone being very rough in nature; no markings could be identified on the stone. Someone has visited this section corner a number of years ago and had driven a steel fence post alongside with a monument sign attached to help perpetuate the section corner location. The sign had fallen to the ground in disrepair as shown in the accompanying photo. No other large stone found and very few small stone are available in this area

## Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this section corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 6 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument. I placed a small mound of stone about the monument using the only stone that was available. I then reset the steel fence post alongside the monument reattaching the monument sign to aid in locating the monument in the future. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on December 8, 2012



Found a stone closely fitting W. B. Barr's description of the stone he set. No visible markings can be identified on the stone. A steel fence post and monument sign in disrepair was present at this corner location.



Brass cap and small mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. I then reset the steel fence post reattaching the monument sign to aid in locating the monument in the future.



Brass Cap as stamped.

This Section corners handheld GPS geographic position.  
44° 46' 27.600" N, 117° 41' 10.080" W NAD83.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James H. Hambleton*

OREGON  
JULY 10, 1964  
JAMES H. HAMBLETON  
645

Renews June 30, 2012