

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 12" x 8" x 8" buried 8 inches in the ground, marked 1/4 on the North side for the one quarter corner common to Sections 15 & 22, T 9 S, R 41 E W.M. Dug pits 18" x 18" x 12", 5 1/2 feet distance East and West of the stone and placed a raised mound of earth 1 1/2 feet high, 3 1/2 feet at base alongside.

## Description of Corner Evidence Found:

At this corner location I found a unique, but broken Basalt stone measuring 12" x 10" x 8", which closely fits the dimension of the stone W. B. Barr said he set. I could not identify any visible markings on the stone. Stone is as shown in the accompanying photo. No other stone of such dimension are located in the area.



Found a unique, but broken Basalt stone measuring 12" x 10" x 8", closely fitting W. B. Barr's description of the stone he set. No visible markings can be identified on the stone.

## Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this 1/4 corner, at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 7 inches above the ground surface. The broken original stone was turned upside down and buried on the North side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. Notice the reference pin located in the background near the top just left of the center of photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Brass Cap as stamped.

This 1/4 corners handheld GPS geographic position.  
44° 46' 27.300" N, 117° 40' 34.320" W NAD83.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on December 8, 2012

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 10, 1964  
JAMES H. HAMBLETON  
645

Renews June 30, 2012

N-15  
9

FILED Dec. 17, 2012  
BAKER COUNTY SURVEYOR  
SURVEY NO. 9-41-15