
## CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## **History of Original Corner Establishment:**

This section corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 12" x 8" x 6" buried 8 inches in the ground for the section corner common to Sections 14, 15, 22 & 23, T 9 S, R 41 E W.M. Stone was marked with 3 notches on the South and 2 notches on the East edges. Dug pits 18" x 18" x 12", 5 1/2 feet distance in each section and placed a raised mound of earth 2 feet high, 4 1/2 feet at base alongside.

## **Description of Corner Evidence Found:**

At this corner location I found a Basalt stone partly buried measuring 12" x 8"x 7", which closely fits the dimension of the stone W. B. Barr said he set. The stone being clearly marked with 3 notches on the South and 2 notches on the East sides as shown in the accompanying photo. I also found a 1 1/2" x 30" iron pipe that was badly bent and of unknown origin lying alongside the stone. A section corner tag was nailed to a fence corner post about 2 feet northwesterly of the stone.



To perpetuate this section corner at the exact location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within

3 inches above the ground surface. The bent iron pipe was left lying on the ground on the North side against the new monument. There are no stone available in the area; therefore the monument stands alone. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven flush with the ground surface. Iron pin is located in a high traffic area.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven flush with the ground surface. Iron pin is located in a high traffic area.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on December 8, 2012



At this Section Corner location I found a marked Basalt stone that measures 12"x 8"x 7". The marked stone closely agreeing as described in W. B. Barr's field notes. Notice the markings 3 notches on the South and 2 notches on the East faces, as I have highlighted using snow to out line the clearly visible chisel marks at the top center of the stone.



Buried monument to within 3 inches of the surface.

Original stone was placed below the surface on the West side of the Brass Cap. No other stone was available in the area; therefore the monument stands alone. I left the original iron pipe I had found lying beside the new monument.



Brass Cap as stamped.

This Section corners handheld GPS geographic position. 44° 46′ 26.700" N, 117° 39′ 57.840" W NAD83.

PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964

JAMES H. HAMBLETON
645

Renews June 30, 2012

SURVEY NO. 9-41-16