
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Volcanic rock 12" x 10" x 5" buried 8 inches in the ground for the one quarter corner common to Sections 3 & 4, T 9 S, R 41 E W.M., marked 1/4 on the West side, dug pit and a raised mound of earth alongside.

Description of Corner Evidence Found:

At this quarter corner location I found a Volcanic stone firmly in place, measuring 12" x 11" x 6". Stone closely fits the dimension of the stone W. B. Barr said he set. The marking 1/4 is clearly visible on the West face of the stone as shown in the accompanying photo. No other evidence is available at the corner.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side with the markings faceing the new monument, the tip of the stone was left exposed above the surface. I placed a small mound of the only stone available in the general area about the monument.

The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 19, 2013.



At this Quarter Corner location I found a marked Volcanic stone that measures 12"x 11"x 6". The marked stone agreeing closely as described in W. B. Barr's field notes. Notice the markings 1/4 as I have highlighted using a black lumber crayon to out line the clearly visible chisel marks.



Buried monument to within 8 inches of the surface.

Original stone was placed upside down with the tip above the surface on the West side of the Brass Cap. Using the only stone available in the general area I placed a very small mound around the monument.



Brass Cap as stamped.

This quarter corners handheld GPS geographic position. 44° 48' 38.280" N, 117° 41' 9.240" W NAD83.

REGISTERED PROFESSIONAL' LAND SURVEYOR

OREGON
JULY 10, 1964

JAMES H. HAMBLETON
645

Renews June 30, 2014

19 C-15 FILED May 20, 2013
BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-17