

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This Section Corner was established by Timothy Davenport, Deputy Surveyor under Contract No. 102 and being dated July 20, 1863. His notes states he set a post for corner to Sections 7,18,12 & 13, T 9 S, R 40 & 41 E W.M.; made a mound of earth and drove a charred stake as per instructions.

Description of Corner Evidence Found:

At this corner location I found no trace of the original corner as described and set by Timothy Davenport, Deputy Surveyor in the year 1863. However I did find strong supportive evidence of a very old historic fence corner, as well as an existing fence corner at the same location, with very old fences running to the North, East and West. Further research reveals this historic fence corner to agree very closely to the GLO survey calls to adjacent GLO corners to the North, East and West. After carefully evaluating the evidence at hand of which I had found the badly rotted remains of a corner post buried deep in the ground, as well as stone placed around its location. Along side there is presently an existing corner post. Also the relationship this location has with the adjacent GLO corners North, East and West, therefore I believe the results to be the best available evidence to the corners original location.

Description of Monument and Accessories

I Established to Perpetuate the Original

Location of Corner:

To perpetuate this Section Corner at the location of the original badly rotted post, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 19, 2013.



Notice the historic fence corner with a straight fence line running over a mile to the North over the distant horizon. It appears this corner was used possibly even to control the property of early homesteaders.



Notice the rotted remains of the original fence post I found buried deep in the ground and where I set the Brass Cap monument. The stone mound is as it appeared before I buried it with soil to help stabilize the stones for the future.



Brass Cap as stamped.

This Section Corners handheld GPS geographic position.
44° 47' 19.800" N, 117° 44' 53.280" W NAD83.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2014

FILED May 20, 2013
BAKER COUNTY SURVEYOR
SURVEY NO. 9-40-712
9-41-18