
## CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## **History of Original Corner Establishment:**

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 12" x 10" x 8" buried 8 inches in the ground for the one quarter corner common to Sections 7 & 18, T 9 S, R 41 E W.M., marked 1/4 on the North side; placed a raised mound rock alongside. Pits impracticable.

## **Description of Corner Evidence Found:**

At this 1/4 corner location I found a Basalt stone measuring 16" x 10" x 8"which somewhat fits the dimension of the stone W. B. Barr said he set. The marking 1/4 is clearly visible on the face of the stone as shown in the accompanying photo. Someone has visited this quarter corner a number of years ago as a mound of stone had been placed around the cornerstone with a steel fence post driven alongside to help perpetuate its location.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. I then reset the steel fence post alongside the mound to aid in locating the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 19, 2013.



At this Quarter Corner location I found a marked Basalt stone that measures 16"x 10"x 8", the marked stone somewhat agreeing as described in W. B. Barr's field notes. Notice the markings 1/4 as I have highlighted using a black lumber crayon to outline the clearly visible chisel marks.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. I then reset the steel fence post alongside the mound to aid in locating the monument.



Brass Cap as stamped

This Quarter Corners handheld GPS geographic position. 44° 47' 19.620" N, 117° 44' 16.620" W NAD83.

REGISTERED PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964

JAMES H. HAMBLETON
645

Renews June 30, 2014

12
J-3

FILED May 20, 2013

BAKER COUNTY SURVEYOR

SURVEY NO. 9-41-19