
## CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## **History of Original Corner Establishment:**

This Section corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 14" x 10" x 7" buried 10 inches in the ground for the Section corner common to Sections 7, 8, 17 & 18, T 9 S, R 41 E W.M., marked with four notches on the South and five notches on the East edges; placed a raised mound rock alongside. Pits impracticable.

## **Description of Corner Evidence Found:**

At this corner location I found a Basalt stone buried in a mound of rock, measuring 15" x 10"x 7", which closely fits the dimension of the stone W. B. Barr said he set. I was unable to identify any markings described by W. B. Barr, with any certainty. Stone as shown in the accompanying photo. Someone has visited this section corner a number of years ago and added a large mound of stone covering this stone to help perpetuate its location. The stone fits closely to the GLO field notes, thus I accepted its location as the original corner set by W. B. Barr.



To perpetuate this Section corner, at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:


Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 19, 2013.



Found large mound of stone at section corner location. Insert photo shows stone measuring 15" x 10" x 7", closely fitting W. B. Barr's description of the stone he claimed to have set. Stone was found and recovered from the center of the large mound as if it was intentionally buried, possibly for protection.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound.



Brass Cap as stamped.

This Section corners handheld GPS geographic position. 44° 47' 19.860" N, 117° 43' 38.400" W NAD83.

PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2014

FILED May 20, 2013
BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-20

13 J-5