
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 16" x 14" x 12" buried 8 inches in the ground for the one quarter corner common to Sections 8 & 17, T 9 S, R 41 E W.M., marked 1/4 on the North side. placed a raised mound rock alongside. Pits impracticable.

Description of Corner Evidence Found:

At this corner location I found a Basalt stone measuring 16" x 14"x 11", which closely fits the dimension of the stone W. B. Barr said he set. The marking 1/4 is dimly visible on the North face of the stone as shown in the accompanying photo. A mound of stone lies along the North side of the corner stone.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and placed on the Westerly side of the new monument. Ground was to rocky to completely bury the stone, thus it appears as shown in the accompanying photo. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. I then set a steel fence post alongside the mound to aid in locating the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 16.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.


Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 19, 2013.



At this Quarter Corner location I found a dimly marked E stone that measures 16"x 14"x 11", the marked stone closely agreeing as described in W. B. Barr's field notes. Notice the markings 1/4 as I have faintly highlighted using a black lumber crayon to outline the clearly visible chisel marks. Insert photo shows original position of the marked 1/4 corner stone and mound.



Brass cap and mound of stone as they appear. The original stone was turned upside down facing the monument I was unable to bury the stone as the ground was too rocky.



Brass Cap as stamped.

This Quarter Corners handheld GPS geographic position. 44° 47' 19.920" N, 117° 43' 1.440" W NAD83.

REGISTERED **PROFESSIONAL** LAND SURVEYOR

OREGON 1964 JAMES H. HAMBLETON 645

Renews June 30, 2014