

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 12" x 10" x 6" buried 8 inches in the ground for the one quarter corner common to Sections 21 & 22, T 9 S, R 41 E W.M., marked 1/4 on the West side. Dug pits 18"x 18"x 12", 5 1/2 ft. distance North and South of stone. Placed a raised mound of earth 1 1/2 ft. high 3 1/2 ft. at base alongside.



Found a stone closely fitting W. B. Barr's description of the stone he set. No visible markings can be identified on the stone. Also I found a small somewhat scattered mound of stone.

Description of Corner Evidence Found:

At this 1/4 corner location I found a Basalt stone measuring 12" x 10" x 8" which somewhat fits the dimension of the stone W. B. Barr said he set. I could not identify any markings on the stone. I also found a small number of stones along side the corner stone. A North - South fence line is located 5 feet to the West of the original stone location. I accepted the stone and mound as the best available evidence for the original corner.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. Notice The reference monument near the upper center of the photo as well as the existing North-South fence line located 5 feet to the West of the corner.

Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.



Brass Cap as stamped.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

This Quarter Corners handheld GPS geographic position.
44° 46' 0.540" N, 117° 41' 10.800" W NAD83.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 21, 2013.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2014

15
P-13

FILED May 20, 2013
BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-22