
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 11" x 8" x 4" buried 8 inches in the ground for the one quarter corner common to Sections 22 & 27, T 9 S, R 41 E W.M., marked 1/4 on the North side. Dug pits 18" x 18" x 12", a distance of 5 1/2 ft. East & West of stone, with a raised mound of earth 1 1/2 ft. high, 3 1/2 ft. at base placed alongside the stone.

Description of Corner Evidence Found:

At this 1/4 corner location I found a Basalt stone measuring 12" x 10" x 7" which somewhat fits the dimension of the stone W. B. Barr said he set. I could not identify any markings on the stone. I also found a mound of stones along side the corner stone. I also found evidence of an old historic fence corner, which appeared to be independent of the mound of stone, but adjacent to the corner stone. I accepted the stone and mound as the best available evidence for the original corner.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 21, 2013.



Found a stone somewhat fitting W. B. Barr's description of the stone he set. No visible markings can be identified on the stone. Also I found a somewhat scattered mound of stone



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. Original stone is buried along the North face of the Brass Cap monument.



Brass Cap as stamped.

This Quarter Corners handheld GPS geographic position. 44° 45' 34.800" N, 117° 40' 34.260" W NAD83.

REGISTERED **PROFESSIONAL** LAND SURVEYOR

OREGON JAMES H. HAMBLETON

Renews June 30, 2014

R-15 9-41-23