
## CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## **History of Original Corner Establishment:**

This Section corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 16" x 10" x 4" buried 11 inches in the ground for the section corner common to Sections 22, 23, 26 & 27, T 9 S, R 41 E W.M. Stone was marked with 2 notches on the South & East edges. Dug pits 18" x 18" x 12", 5 1/2 ft. distance in each section. Placed a raised mound of earth 2 ft. high 4 1/2 ft. at base alongside the stone.

## **Description of Corner Evidence Found:**

At this corner location I found what I would call a Quartzite type stone firmly in place buried about 7 inches in the ground. The stone measuring 14" x 9"x 6", which somewhat fits the dimension of the stone W. B. Barr said he set. I was able to clearly identify the markings described by W. B. Barr. Stone and marks are shown in the accompanying photo. Someone has visited this section corner a number of years ago and added a steel fence post to help perpetuate its location. There are no other stone in the general area of this corner.



To perpetuate this Section corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument leaving the tip of the stone exposed as there are no stone available to make a mound. I then reset the steel fence post alongside the mound to aid in locating the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 21, 2013.



At this Section Corner location I found a marked Quartzite type stone that measures 14"x 9"x 6", somewhat agreeing as was described in W. B. Barr's field notes. Notice the markings 2 notches on the South and 2 notches on the East faces, as I have highlighted using black lumber crayon to outline the clearly visible chisel marks at the center face of the stone.



Buried monument to within 8 inches of the surface.

Original stone was placed upside down with the tip above the surface on the West side of the Brass Cap. No other stone was available to make a mound. I then reset the steel fence post alongside the monument to aid in locating the monument in the future.



Brass Cap as stamped

This Section corners handheld GPS geographic position.  $44^{\circ}$  45' 34.440" N, 117° 39' 57.720" W NAD83.

REGISTERED PROFESSIONAL' LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2014

17 FILED May 20, 2013
R-17 BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-24