

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 16" x 10" x 8" buried 11 inches in the ground for the one quarter corner common to Sections 26 & 27, T 9 S, R 41 E W.M., marked 1/4 on the West side. Dug pits 18" x 18" x 12", 5 1/2 ft. distance North & South of stone; placed a raised mound of earth 1 1/2 ft. high, 3 1/2 ft. at base along side the stone.

## Description of Corner Evidence Found:

At this corner location I found a Quartzite type stone firmly in place buried nearly flush with the ground. The stone measuring 16" x 10" x 6", which fits closely to the dimension of the stone W. B. Barr said he set. I was able to clearly identify the 1/4 markings described by W. B. Barr. Stone and marks are shown in the accompanying photo. There are no other stone in the general area of this corner.



At this Quarter Corner location I found a marked Quartzite stone that measures 16"x 10"x 6". The marked stone somewhat agreeing as described in W. B. Barr's field notes. Notice the markings 1/4 as I have highlighted using a black lumber crayon to outline the clearly visible chisel marks.

## Description of Monument and Accessories

### I Established to Perpetuate the Original

### Location of Corner:

To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument, with the tip of the stone exposed above the ground surface. I then placed a very small mound of the only stone available in the general area alongside the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 21, 2013.



Buried monument to within 8 inches of the surface. Original stone was placed upside down with the tip above the surface on the West side of the Brass Cap. Using the only stone available in the general area I placed a very small mound around the monument.



Brass Cap as stamped.

This quarter corners handheld GPS geographic position.  
44° 45' 9.120" N, 117° 39' 58.140" W NAD83.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James H. Hambleton*

OREGON  
JULY 10, 1964  
JAMES H. HAMBLETON  
645

Renews June 30, 2014