
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 13" x 9" x 5" buried 9 inches in the ground for the one quarter corner common to Sections 2 & 11, T 9 S, R 41 E W.M., marked 1/4 on the North side. Dug pits 18" x 18" x 12", 5 1/2 ft. distance North & South of stone; placed a raised mound of earth 1 1/2 ft. high, 3 1/2 ft. at base along side the stone.

Description of Corner Evidence Found:

At this quarter corner location I found a Basalt stone firmly in place buried to within 6 inches above the surface of the ground. The stone measuring 12" x 8" x 7", which somewhat fits closely to the dimension of the stone W. B. Barr said he set. I was able to clearly identify the 1/4 markings on the North face of the stone as described by W. B. Barr. Stone and marks are shown in the accompanying photo. There are no other stone in the general area of this corner.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument, with the tip of the stone exposed above the ground surface. There are no other stone available in the general area of the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 26, 2013.

BAKER COUNTY SURVEYOR SURVEY NO. 9-41-26



At this Quarter Corner location I found a marked Basalt stone that measures 12"x 8"x 7", the marked stone somewhat agreeing as described in W. B. Barr's field notes. Notice the markings 1/4 as I have highlighted using a black lumber crayon to outline the clearly visible chisel marks.



Buried monument to within 8 inches of the surface.

Original stone was placed upside down with the tip above the surface on the North side of the Brass Cap. Using the only stone available in the general area I placed a very small mound around the monument. There are no other stone available in the general area of the monument.



Brass Cap as stamped

This quarter corners handheld GPS geographic position. 44° 48' 12.600" N, 117° 39' 18.480" W NAD83.

REGISTERED
PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964

JAMES H. HAMBLETON
645

Renews June 30, 2014

20 E-19