
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This Section Corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 12" x 10" x 6" buried 8 inches in the ground for the section corner common to Sections 1, 2, 11 & 12, T 9 S, R 41 E W.M., marked with 5 notches on the South and 1 notch on the East edges. Dug pits 18" x 18" x 12", 5 1/2 ft. distance in each section. Placed a raised mound of earth 2 ft. high 4 1/2 ft. at base alongside the stone.

Description of Corner Evidence Found:

At this Section corner location I found a Basalt stone partly buried measuring 15" x 9"x 7", which somewhat closely fits the dimension of the stone W. B. Barr said he set. The stone being clearly marked with 5 notches on the South and 1 notch on the East sides as is shown in its original position undisturbed in the accompanying photo. Also I found evidence of an old historic fence corner adjacent to this original stone.



To perpetuate this Section corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 26, 2013.



I found a Basalt stone measuring 15" x 9" x 7" as shown in it's undisturbed position. The 5 notches are at uniform distances along the top edge of the stone, highlighted by the light colored soil in the background. The 1 notch appears on the backside facing the ground.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound.



Brass Cap as stamped

This Section corners handheld GPS geographic position. 44° 48' 13.440" N, 117° 38' 41.520" W NAD83.

PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2014

FILED May 22, 2013
BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-27