
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 20" x 10" x 8" buried 15 inches in the ground for the one quarter corner common to Sections 1 & 12, T 9 S, R 41 E W.M., marked 1/4 on the North side. Dug pits 18" x 18" x 12", a distance of 5 1/2 ft. East & West of stone, with a raised mound of earth 1 1/2 ft. high, 3 1/2 ft. at base placed alongside the stone.

Description of Corner Evidence Found:

At this Quarter corner location I found a Basalt stone lying on its side partially buried in the ground. The stone measuring 20" x 12" x 10", which somewhat fits closely to the dimension of the stone W. B. Barr said he set. I was able to clearly identify the 1/4 markings described by W. B. Barr. Stone and marks are shown in the accompanying photo. There are no other stone in the general area of this corner.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument, leaving the tip of the stone exposed as there are no stone available to make a mound. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 26, 2013.



At this Quarter Corner location I found a marked Basalt stone that measures 20"x 12"x 10". The marked stone somewhat agreeing as described in W. B. Barr's field notes. Notice the markings 1/4 as I have highlighted using a black lumber crayon to out line the clearly visible chisel marks.



Buried monument to within 8 inches of the surface.

Original stone was placed upside down with the tip above the surface on the North side of the Brass Cap. No other stone are available in the general area of this monument.



Brass Cap as stamped.

This quarter corners handheld GPS geographic position. 44° 48' 13.440" N, 117° 38' 4.380" W NAD83.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2014

FILED May 22, 2013
BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-28