
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 12" x 10" x 6" buried 8 inches in the ground for the one quarter corner common to Sections 11 & 12, T 9 S, R 41 E W.M., marked 1/4 on the West side. Dug pits 18" x 18" x 12", 5 1/2 ft. distance North & South of stone; placed a raised mound of earth 1 1/2 ft. high, 3 1/2 ft. at base along side the stone.

Description of Corner Evidence Found:

At this quarter corner location I found a Basalt stone firmly in place about 6 inches in the ground. Stone measuring 12" x 11" x 8"which somewhat closely fits the dimension of the stone W. B. Barr said he set. The marking 1/4 is clearly visible on the West face of the stone as shown in the accompanying photo. No other evidence is available at the corner.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument, with the tip of the stone exposed above the ground surface. There are no other stone available in the general area of this monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March $26,\,2013.$



At this Quarter Corner location I found a marked Basalt stone that measures 12"x 11"x 8", the marked stone somewhat agreeing as described in W. B. Barr's field notes. Notice the markings 1/4 as I have highlighted using a black lumber crayon to outline the clearly visible chisel marks.



Buried monument to within 8 inches of the surface.

Original stone was placed upside down with the tip above the surface on the North side of the Brass Cap. There are no other stone available in the general area of the monument.



Brass Cap as stamped.

This quarter corners handheld GPS geographic position. 44° 47' 46.920" N, 117° 38' 41.460" W NAD83.

PROFESSIONAL:
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2014

FILED May 22, 2013
BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-29

23 G-21