
## CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## **History of Original Corner Establishment:**

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 388 and being dated May 7, 1881. His notes states he set a Basalt rock 14" x 7" x 6" buried 8 inches in the ground for the one quarter corner common to Sections 12 & 7, T 9 S, R 41 & 42 E W.M., marked 1/4 on the West side, placed a raised mound rock alongside as per instructions.

## **Description of Corner Evidence Found:**

At this corner location I found a marked Basalt stone, measuring 14" x 8"x 7", the stone was lying on it's side. The marking 1/4 is barley visible on the Westerly face of the stone as shown in the accompanying photo. The Basalt stone closely fits the dimension of the stone W. B. Barr said he set. A mound of stone was alongside as shown in the accompanying photo.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 10 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 8 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 8 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 8 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 8 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 27, 2013.



At this Quarter Corner location I found a marked Quartzite stone that measures 14"x 8"x 7" and a mound of stone. The markings 1/4 was barley visible. The marked stone closely agreeing as described in W. B. Barr's field notes.



Buried the monument to within 10 inches of the surface Original stone was placed upside down and placed on the West side of the Brass Cap. The remains of the original mound of stone was then placed around the Brass Cap. Notice the reference pin located in the background near the top center of photo



Brass Cap as stamped.

This 1/4 corners handheld GPS geographic position. 44° 47' 48.180" N, 117° 37' 33.420" W NAD83.

REGISTERED PROFESSIONAL' AND SURVEYOR

OREGON JAMES H. HAMBLETON 645

Renews June 30, 2014

26 G-25