

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of Original Corner Establishment:

This quarter corner was established by W. B. Barr, Deputy Surveyor under Contract No. 443 and being dated May 29, 1882. His notes states he set a Basalt rock 18" x 12" x 8" buried 12 inches in the ground for the one quarter corner common to Sections 12 & 13, T 9 S, R 41 E W.M., marked 1/4 on the North side, placed a raised mound rock alongside. Pits impracticable.

## Description of Corner Evidence Found:

At this Quarter corner location I found a Basalt stone measuring 18" x 11" x 8", which closely fits the dimension of the stone W. B. Barr said he set. Though very dim, there are actually double 1/4 markings visible on the North face of the stone, as shown in the accompanying photo. A mound of stone lies somewhat scattered along the North side of the corner stone.



At this Quarter Corner location I found a very dimly double marked Basalt stone that measures 18"x 11"x 8"; the marked stone closely agreeing as described in W. B. Barr's field notes. Notice the very dim double 1/4 markings as I have lightly highlighted using a black lumber crayon to outline the marks.



Buried the monument to within 10 inches of the surface. Original stone was placed upside down and placed on the North side of the Brass Cap. I placed a large mound of stone around the brass cap monument.

## Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 10 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument. I then placed a large mound of stone a three feet in diameter about the monument surrounding the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Brass Cap as stamped.

This quarter corners handheld GPS geographic position.  
44° 47' 20.040" N, 117° 38' 3.960" W NAD83.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 27, 2013.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 10, 1964  
JAMES H. HAMBLETON  
645

Renews June 30, 2014