
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This Section corner was established by W. B. Barr, Deputy Surveyor under Contract No. 388 and being dated May 7, 1881. His notes states he set a Basalt rock 16" x 10" x 6" common to Sections 12, 13, 7 & 18, T 9 S, R 41 & 42 E W.M., placed a raised mound rock alongside as per instructions.

Description of Corner Evidence Found:

At this section corner location I found a Basalt stone buried in a mound of rock measuring 14" x 11"x 9", which somewhat fits the dimension of the stone W. B. Barr said he set. Due to the rough texture of the stone I was unable to identify with any certainty any markings as described by W. B. Barr. Stone is as shown in the accompanying photo. Someone has visited this section corner a number of years ago and added a steel fence post to help perpetuate its location.



To perpetuate this 1/4 corner at the location of the stone, I set a 2 1/2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. I then reset the steel fence post alongside the mound to aid in locating the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on March 27, 2013.



Found a stone somewhat fitting W. B. Barr's description of the stone he set. No visible markings on the stone can be identified with any certainty. Also I found a somewhat scattered mound of stone and a steel fence post.



Brass cap and mound of stone as they appeared before covering the mound with soil to assist in protecting and stabilizing the mound. I then reset the steel fence post alongside the mound to aid in locating the monument.



Brass Cap as stamped.

This quarter corners handheld GPS geographic position. 44° 47' 22.139" N, 117° 37' 33.600" W NAD83.

PROFESSIONAL'
LAND SURVEYOR

OREGON JULY 10, 1964 JAMES H. HAMBLETON 645

Renews June 30, 2014

25 J-25 FILED May 22, 2013
BAKER COUNTY SURVEYOR
SURVEY NO. 9-41-32