

A PARCEL IN NE $\frac{1}{4}$ NW $\frac{1}{4}$ OF SECTION 22, T. 9 S., R. 45E., W.M.

Survey was performed for William Dorrah, Richland, Oregon on July 27 and August 14, 1979, based on description furnished by Land Title Insurance Company of Baker, Oregon.

Cardinal directions in the description are intended to follow sectional subdivision lines: "Commencing at a point 50 rods South of the North-east corner of said NE $\frac{1}{4}$ NW $\frac{1}{4}$ is interpreted to mean the point of beginning is on the East line of the NE $\frac{1}{4}$ NW $\frac{1}{4}$. The closing course of N. 39° 01' 10" W., is calculated to be 1059.72 feet. The description for this course reads "Northwesterly 64 rods".

The point of beginning, the North $\frac{1}{4}$ corner of Section 22 is marked by a one-inch diameter axle shaft, buried about 8-inches below the road surface, found as described.

The meridian used for this survey is based on filed Map of Survey No. 9-45-10, which in turn was determined by a solar observation.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley

OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

Hanley Engineering
Baker, Oregon

9-45-24