


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W. B. Barr under GLO contract no. 355 dated June 14, 1880.

Surveyor General records state:

Set stake 4 ft long 4 ins diam 18 ins in the ground for 1/4 sec corner, dug pits and raised mound as per instructions.



Description of corner evidence found:

At approximate corner location found a stone marked 1/4 in place at base of fence corner from which the fence lines run East and South.

It appears that this stone has been marked in a professional manner and is presumed that the original wood post corner monument has been remonumented by competent authority with no remonumentation record filed.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2 inch diameter brass cap on a 1 inch iron pipe 31 inches long and projecting 6 inches out of the ground with a surrounding rock mound. Buried stone alongside.

Brass cap marked thus:      T 9 S R 40 E

$\frac{1}{4}$	$\frac{S 23}{S 26}$
---------------	---------------------

CS 1982

I hereby certify that the above described corner monument was properly established under my supervision and witnessed by Brad Gordon, Jim DeMastus and Tom Fisk.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James D. Hanley*

OREGON  
SEPTEMBER 23, 1977  
JAMES D. HANLEY  
1206

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)