

## RECORD OF LAND CORNER MONUMENTATION

Description of corner evidence found and history:

I found a bridge spike of unknown origin set in the center of Baker County Road No. 980-Sawmill Lane which has been accepted as the section corner by other surveys.

### DIAGRAM

T9S	R45E
S15	S14
S22	S23
PLS 699 2004	

Description of monument and accessories I established to perpetuate the original location of this corner:

I replaced the spike with a 30" long 1" galvanized pipe with a 2 1/2" brass cap 34" in the ground so that the cap is 4" below the road surface and made ties to the following references:

- A power pole bears NE, 70.6 feet;
- The SE corner of a RR tie post bears NW, 50.85 feet;
- The South end of an 18" culvert bears SW, 35.6 feet;
- and the West end of a car frame fence brace bears SE, 69.35 feet.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Leland Lee Myers*

OREGON  
JULY 9, 1985  
LELAND LEE MYERS  
699

Renewal Date 1/1/2007

BAKER COUNTY SURVEYOR

RECEIVED FEBRUARY 14, 2005

ACCEPTED FEBRUARY 14, 2005

SURVEY No. 9-45-76

*CP*  
DWG. No. 112

INDEX No. T9S R45E N-17