

## RECORD OF LAND CORNER MONUMENTATION

Description of corner evidence found and history:

No evidence of the original corner and there is no record that it has ever been perpetuated or reestablished. The corner location is in farm land that has been cultivated.

### **DIAGRAM**

T9S R45E  
S14  
1/4 ———  
S23  
  
PLS 699  
2004

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 30" long 1" galvanized pipe with a 2 1/2" brass cap 28" in the ground at the proportionate distance between the two section corners on the South edge of a small irrigation ditch. References are as follows:  
A magnetic DEEP with yellow ribbon is set in a fence line 1-foot under the ground in a WSW direction 7.85' from the monument.  
A round corner post bears Southerly across an access road 29.05'.  
A magnetic DEEP with red ribbon is set in a fence line 8" under the ground in an ESE direction 6.6'.  
A steel gate post with a steel brace is 65.1' in an ESE direction.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Leland Lee Myers*

OREGON  
JULY 9, 1985  
LELAND LEE MYERS  
699

Renewal Date 1/1/2007

BAKER COUNTY SURVEYOR

RECEIVED FEBRUARY 14, 2005

ACCEPTED FEBRUARY 14, 2005

SURVEY No. 9-45-77

*CP*  
DWG. No. 113

INDEX No. **T9S R45E N-19**