

RECORD OF LAND CORNER MONUMENTATION

Description of corner evidence found and history:

I found surveys that used the section corner for the division of sections, but the corner had never been monumented. The corner position is in the center of Moody Lane and I did not find any evidence of any kind for the corner.

DIAGRAM

T9S	R45E
S14	S13
S23	S24
PLS 699	
2004	

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 30" long 1" galvanized pipe with a 2 1/2" brass cap 36" in the ground so that the cap is 6" below the road surface in line with fences to the East and West and made ties to the following references:

- The SW corner of a RR tie post bears NE, 30.25 feet;
- The SE corner of a RR tie gate post bears NW, 31.9 feet;
- The SW corner of concrete ditch weir bears SW, 28.4 feet;
- and the NW corner of a RR tie post bears SE, 32.85 feet.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 9, 1965
LELAND LEE MYERS
699

Renewal Date 1/1/2007

BAKER COUNTY SURVEYOR

RECEIVED FEBRUARY 14, 2005

ACCEPTED FEBRUARY 14, 2005

SURVEY No. 9-45-78

CP
DWG No. 114

INDEX No. T9S R45E N-21