


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

A red fir post $3\frac{1}{2}$ " long, 4" square, set 18" in the ground with mound of rocks, scribed A. No. 1 W.C.-546 whence, A red fir 14" diam. bears N. $14^{\circ} 28'$ W. 10.93 ft. A red fir 12" diam. bears N. $72^{\circ} 04'$ E. 16.39 ft. Discovery Cut bears S. $62^{\circ} 22'$ E. 808 ft.



Description of corner evidence found:

Found a rock mound about 3' in diameter and 18" high in good condition with a portion of the original 4x4 corner post in the mound. Both BT's are standing, but the NE one is dead.

Description of monument and accessories I established to perpetuate the original location of this corner

Set a 2" aluminum cap on a 1"x30" galvanized pipe, which is split for 8", in the center of the rock mound. The D. Fir BT's have grown to 16" and 14" respectively and were marked with Bearing Tree tags with the information listed above for each tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Leland Lee Myers

OREGON
JULY 9, 1965
LELAND LEE MYERS
699

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 19 day of July, 1973, at 11 o'clock A.M., (signed)
by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)