

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set was post 3 ft. long, 5 ins. sq., 18 in. in the ground marked 8-555 HF from which:

A fir 8 in. dia. bears S 83 35 W, 43.8 ft. scribed 8-555-HF BT.

A fir 28 in. dia. bears N 62 E, 27.5 ft. scribed 8-555-HF BT.

DIAGRAM

Harold F
MS 555

8
1973
645

Description of corner evidence found:

At corner location I found an old badly rotted post from which I found a fir that has grown from 8 in. to 22 in. in dia. with blaze grown over, did not open. Also I found a dead fir, that has grown from 28 in. to 35 in. in dia. - the blaze had been opened previously.

Description of monument and accessories I established to perpetuate the original location of this corner

As the bearing trees agree with the original survey, I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap in the ground with a mound of stone around the base. Cap marked as shown in the diagram.

New bearing trees:

A pine 14 in. dia. bears S 75E, 15.6 feet, scribed Har. F 8 MS 555 BT with a brass tag stamped LS 645.

A pine 12 in. dia. bears S 03 30 W, 20.4 ft., scribed Har. F 8 MS 555 BT with a brass tag stamped LS 645.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

I hereby certify the above corner monument was re-established as herein above, in October 1973.

Witness: *Brad D. Johnson*

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 30 day of November, 1973, at 9:30 o'clock A.m., (signed)
by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

10-35-31