

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set was a post 5 in. sq. 3 ft. long set 18 in. in ground with a mound of earth along side, scribed 10 555 HF from which:

a fir 28 in. dia. bears N 02 30 E, 34.7 ft., scribed 10-555HF BT.

a pine 36 in. dia. bears S 11 E, 36.5 ft., scribed 10-555 HF BT.

DIAGRAM

Harold F
MS 555

10
1973
645

Description of corner evidence found:

At corner location I found a small mound and a fir 34 in. dia., also I found the stump of the 36. in. pine.

Description of monument and accessories I established to perpetuate the original location of this corner

As the evidence agrees with the original survey, I set a 36 in. long, 2 in. galv. iron pipe with a 2 in. brass cap in a mound of stone. Cap marked as shown in diagram.

New bearing tree:

a red fir 8 in. dia. bears S 75 E, 21.2 feet scribed Har. F-10 MS 555 BT with a brass tag stamped LS 645.

I hereby certify the above corner monument was re-established as herein above, in October 1973.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Witness: *Brad D. Johnson*

James H. Hambleton
OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 30 day of November, 1973, at 9:30 o'clock A.m., (signed)
..... by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

SURVEY NO. 10-35-33