

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

A post 6 in. sq. 3 ft. long set 18 in. in ground with raised mound of earth and scribed 11-555 HF from which:

a fir 24 in. dia. bears N 78 E, 2.4 ft. scribed 11-555 HF BT.

a fir 24 in. dia. bears N 87 W, 28 ft. scribed 11-555 HF BT.

DIAGRAM

Harold F
MS 555

11

1973
645

Description of corner evidence found:

At corner location I found both bearing trees alive and in good condition but no evidence of post or mound as ground is steep.

Description of monument and accessories I established to perpetuate the original location of this corner

As the evidence I found agrees with the original survey, I set a 36 in. long, 2 in. galv iron pipe with 2 in. brass cap in the ground with a mound of stone. Cap marked as shown in diagram.

Set no new bearing trees.

I hereby certify the above corner monument was re-established as herein above, in October 1973.

Witness: *Brad D. Johnson*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of *County Surveyor* County of *Baker*
State of *Oregon*, I hereby certify that the within instrument was filed in this office
for record on the *30* day of *November*, 19 *73*, at *9:30* o'clock *A.* m., (signed)
..... by *Tom Hanley*
(COUNTY OFFICIAL) (DEPUTY)

SURVEY NO. *10-35-34*