

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

A post 6 in. sq. 3 1/2 ft. long, set 18 in. in ground in raised mound of earth, scribed 12-555 HF from which:

a fir 18 in. dia. bears S 45 E, 39.2 ft. scribed 12-555 HF BT.

a fir 25 in. dia. bears N 15 E, 16.0 ft. scribed 12-555 HF BT.

DIAGRAM

Harold F
MS 555

12
1973
645

Description of corner evidence found:

At corner location I found mound of earth and stone and the 25 in. bearing tree which has grown to 36 in. dia. Other BT is gone entirely.

Description of monument and accessories I established to perpetuate the original location of this corner

As the evidence I found agrees with the original survey, I set a 36 in. long, 2 in. galv. iron pipe with a 2 in. brass cap, in the ground with a mound of stone around the base. Cap marked as shown in the diagram.

New bearing tree:

a white fir 6 in. dia. bears N 80 W, 21 ft. scribed HAR-F-12 MS 555 BT. with a brass tag stamped LS 645.

I hereby certify the above corner monument was re-established as herein above, in October 1973.

Witness:

Brad D. Johnson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 30 day of November, 1973, at 9:30 o'clock A.m., (signed)
by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

Sub. No. 10-35-35