

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set was a post 5 in. sq. 3.5 ft. long set 18 in in the ground, surrounded by a mound of earth scribed 2-555 HF. from which:

a fir 30 in. in dia. bears N 69 E, 57.3 ft. scribed 2-555 HF BT.

DIAGRAM

Harold F
MS 555

2
1973
645

Description of corner evidence found:

At the corner location I found a mound of stone with a post and two bearing trees. A 30 in. fir dead and rotted away with the blaze showing in the bark. Also a bearing tree with scribing 2-555 HF BT - no notes for this tree.

Description of monument and accessories I established to perpetuate the original location of this corner

The mound of stone and post agree to the original survey. Therefore, I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap in the ground with a mound of stone. Cap marked as shown in the diagram.

Old bearing tree:

a pine 24 in. dia. bears S 31 E, 30.4 ft. scribed 2-555 HF BT.

New bearing tree:

a fir 10 in. in dia. bears N 68 30 E, 32.9 ft., scribed Harold F-2 MS 555 BT with a brass tag stamped LS 645.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: Brad D. Johnson

OREGON
JULY 10, 1972
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 30 day of November, 1973, at 9:20 o'clock A.m., (signed)
by Torn Hanley
(COUNTY OFFICIAL) (DEPUTY)

10-35-37