

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set a post 5 in. sq. 3.5 ft. long, set 18 in. in the ground with a raised mound of earth, scribed 3-555 HF from which:

a fir 18 in. in dia. bears N 75 E, 5 ft. scribed 3-555 HF BT.

a fir 5 in. in dia. bears S 86 W, 2 ft. scribed 3-555 HF BT.

DIAGRAM

Harold F
MS 555
3
1973
645

Description of corner evidence found:

At corner location I found a mound of earth and stone and an old rotted post, with one 32 in. fir with a blaze grown over. No other BT.

Description of monument and accessories I established to perpetuate the original location of this corner

As the evidence agrees with the original survey, I set a 36 in. long 2 in. galv. iron pipe with a 2 in. brass cap in the ground with a raised mound of stone. Cap marked as shown in the diagram.

New bearing tree:

a fir 9 in. dia. bears N 36 W, 8.0 feet, scribed Har. F-3-555 BT with a brass tag stamped LS 645.

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: Brad D. Johnson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of *County Surveyor* County of *Baker*
State of *Oregon*, I hereby certify that the within instrument was filed in this office
for record on the *30* day of *November*, 1973, at *9:30* o'clock *A.*m., (signed)
by *Tom Hambley*
(COUNTY OFFICIAL) (DEPUTY)

10-35-38