

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1904 by August W. Mohr deputy Mineral Surveyor.

Set a fir post 5 in. sq. 3.5 ft. long set 18 in. in the ground surrounded by a mound of earth scribed 4-555 HF from which:

a fir 24 in. dia. bears N 48 E 3.5 ft. scribed 4-555 HF BT.

DIAGRAM

Harold F
MS 555

4

1973
645

Description of corner evidence found:

At corner location I found a mound of earth and stone with a stump of a tamarack scribed 4-555 HF BT.

Description of monument and accessories I established to perpetuate the original location of this corner

As the evidence checked to the bearing and distance of the original survey, I set a 36 in. long, 2 in. galv. iron pipe with a 2 in. brass cap in the ground with a mound of stone. Cap marked as shown in the diagram.

New bearing trees:

a fir 18 in. dia. bears N 37 W, 27.5 ft, scribed Har. F-4-555 BT with a brass tag stamped LS 645.

a spruce 18 in. dia. bears S 20 W, 34.4 ft. scribed Har. F-4-555 BT with a brass tag stamped LS 645.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

I hereby certify the above corner monument was re-established as herein above, in Oct. 1973.

Witness: *Brad D. Johnson*

Office of *County Surveyor* County of *Baker*
State of *Oregon*, I hereby certify that the within instrument was filed in this office
for record on the *30* day of *November*, 19*73*, at *9:30* o'clock *A*.m., (signed)
..... by *Tom Hawley*
(COUNTY OFFICIAL) (DEPUTY)

10-35-39